

## ประกาศกระทรวงอุตสาหกรรม

ฉบับที่ ๔๙๕๔ (พ.ศ. ๒๕๖๐)

ออกตามความในพระราชบัญญัติมาตรฐานผลิตภัณฑ์อุตสาหกรรม

พ.ศ. ๒๕๑๑

เรื่อง ยกเลิกมาตรฐานผลิตภัณฑ์อุตสาหกรรม

ภาชนะบรรจุก๊าซทนความดันแบบไม่มีตะเข็บ

และกำหนดมาตรฐานผลิตภัณฑ์อุตสาหกรรม

ถังก๊าซ - ถังก๊าซเหล็กกล้าไม่มีตะเข็บประเภทบรรจุก๊าซ - การออกแบบ การทำและการทดสอบ

เล่ม ๑ ถังก๊าซเหล็กกล้าชุบและอบคืนตัวที่มีค่าความต้านแรงดึง

น้อยกว่า 1 100 MPa

โดยที่เป็นการสมควรปรับปรุงมาตรฐานผลิตภัณฑ์อุตสาหกรรม ภาชนะบรรจุก๊าซทนความดันแบบไม่มีตะเข็บ มาตรฐานเลขที่ มอก. 359 - 2530

อาศัยอำนาจตามความในมาตรา ๑๕ แห่งพระราชบัญญัติมาตรฐานผลิตภัณฑ์อุตสาหกรรม พ.ศ. ๒๕๑๑ ซึ่งแก้ไขเพิ่มเติมโดยพระราชบัญญัติมาตรฐานผลิตภัณฑ์อุตสาหกรรม (ฉบับที่ ๗) พ.ศ. ๒๕๕๘ รัฐมนตรีว่าการกระทรวงอุตสาหกรรมออกประกาศยกเลิกประกาศกระทรวงอุตสาหกรรม ฉบับที่ ๔๙๔ (พ.ศ. ๒๕๒๓) ออกตามความในพระราชบัญญัติมาตรฐานผลิตภัณฑ์อุตสาหกรรม พ.ศ. ๒๕๑๑ เรื่อง กำหนดมาตรฐานผลิตภัณฑ์อุตสาหกรรม ภาชนะบรรจุก๊าซทนความดันแบบไม่มีตะเข็บ ลงวันที่ ๒๙ ธันวาคม ๒๕๒๓ และประกาศกระทรวงอุตสาหกรรม ฉบับที่ ๑๒๗๔ (พ.ศ. ๒๕๓๐) เรื่อง แก้ไขมาตรฐานผลิตภัณฑ์อุตสาหกรรม ภาชนะบรรจุก๊าซทนความดันแบบไม่มีตะเข็บ (แก้ไขครั้งที่ ๑) ลงวันที่ ๑ พฤศจิกายน ๒๕๓๐ และกำหนดมาตรฐานผลิตภัณฑ์อุตสาหกรรม ถังก๊าซ - ถังก๊าซเหล็กกล้าไม่มีตะเข็บประเภทบรรจุก๊าซ - การออกแบบ การทำและการทดสอบ เล่ม ๑ ถังก๊าซเหล็กกล้าชุบและอบคืนตัวที่มีค่าความต้านแรงดึงน้อยกว่า 1 100 MPa มาตรฐานเลขที่ มอก. 359 เล่ม 1 - 2559 ไว้ ดังมีรายละเอียดต่อท้ายประกาศนี้

ทั้งนี้ ให้มีผลตั้งแต่วันที่ประกาศในราชกิจจานุเบกษาเป็นต้นไป

ประกาศ ณ วันที่ ๒๔ มกราคม พ.ศ. ๒๕๖๐

อุตตม สาวนายน

รัฐมนตรีว่าการกระทรวงอุตสาหกรรม

# มาตรฐานผลิตภัณฑ์อุตสาหกรรม

## ถังก๊าซ – ถังก๊าซเหล็กกล้าไม่มีตะเข็บประเภท

### บรรจุก๊าซซ่ำ – การออกแบบ การทำ

### และการทดสอบ

#### เล่ม 1 ถังก๊าซเหล็กกล้าชุบและอบคืนตัวที่มีค่าความต้าน

#### แรงดิ่งน้อยกว่า 1 100 MPa

#### 1. ขอบข่าย

มาตรฐานผลิตภัณฑ์อุตสาหกรรมนี้ กำหนดคุณลักษณะที่ต้องการสำหรับ วัสดุ การออกแบบ การทำและการเก็บงาน กระบวนการทำ การตรวจสอบและการทดสอบ ที่ผู้ทำถังก๊าซเหล็กกล้าไม่มีตะเข็บประเภทบรรจุก๊าซซ่ำ ที่ความจุน้ำตั้งแต่ 0.5 L ถึง 150 L สำหรับก๊าซอัด ก๊าซเหลวและก๊าซอะเซทิลีน (dissolved gases)

มาตรฐานผลิตภัณฑ์อุตสาหกรรมนี้ ครอบคลุมถังก๊าซที่มีค่าความต้านแรงดิ่งจริง (actual tensile strength,  $R_{ma}$ )  $R_{ma} < 1\ 100\text{ MPa}$

หมายเหตุ 1 ถังก๊าซที่มีความจุน้ำน้อยกว่า 0.5 L และความจุน้ำระหว่าง 150 L ถึง 500 L สามารถทำและรับรอง ตามมาตรฐานผลิตภัณฑ์อุตสาหกรรมนี้ได้

หมายเหตุ 2 ถังก๊าซเหล็กกล้าชุบและอบคืนตัวที่มีค่าความต้านแรงดิ่งสูงสุดเท่ากับหรือมากกว่า 1 100 MPa ดู มอก.359 เล่ม 2 สำหรับถังก๊าซเหล็กกล้าอบปกติ ดู มอก.359 เล่ม 3

#### 2. เอกสารอ้างอิง

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 2.

#### 3. ศัพท์และบทนิยาม

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 3.

#### 4. สัญลักษณ์

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 4.

#### 5. การตรวจสอบและการทดสอบ

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 5.

#### 6. วัสดุ

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 6.

## **7. การออกแบบ**

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 7.

## **8. การทำและการเก็บงาน**

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 8.

## **9. กระบวนการรับรองแบบ**

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 9.

## **10. การทดสอบรุ่มผลิต**

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 10.

## **11. การทดสอบทุกถั่ง/การสอบทุกถั่ง**

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 11.

## **12. การรับรอง**

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 12.

## **13. การทำเครื่องหมาย**

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ 13.

## **ภาคผนวก**

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 ข้อ Annex A Annex B Annex C และ Annex D

## **บรรณานุกรม**

รายละเอียดให้เป็นไปตาม ISO 9809-1 : 2010 Bibliography

© ISO 2006

เอกสารนี้เป็นสิทธิ์ของ ISO หากมิได้กำหนดไว้เป็นอย่างอื่นห้ามนำมาตรฐานฉบับนี้หรือส่วนหนึ่งส่วนใดไปทำซ้ำหรือใช้ประโยชน์ในรูปแบบ หรือโดยวิธีใดๆ ไม่ว่าจะเป็นรูปแบบอิเล็กทรอนิกส์หรือทางกล รวมถึงการถ่ายสำเนาถ่ายไมโครฟิล์มโดยไม่ได้รับอนุญาตเป็นลายลักษณ์อักษรจาก ISO ตามที่อยู่ข้างล่างหรือจากสมาชิก ISO ในประเทศของผู้ร้องขอ

ISO copyright office

Case postale 56 • CH-1211 Geneva 20

Tel. + 41 22 749 01 11

Fax + 41 22 749 09 47

E-mail [copyright@iso.org](mailto:copyright@iso.org)

Web [www.iso.org](http://www.iso.org)



**PDF disclaimer**

This PDF file may contain embedded typefaces. In accordance with Adobe's licensing policy, this file may be printed or viewed but shall not be edited unless the typefaces which are embedded are licensed to and installed on the computer performing the editing. In downloading this file, parties accept therein the responsibility of not infringing Adobe's licensing policy. The ISO Central Secretariat accepts no liability in this area.

Adobe is a trademark of Adobe Systems Incorporated.

Details of the software products used to create this PDF file can be found in the General Info relative to the file, the PDF-creation parameters were optimized for printing. Every care has been taken to ensure that the file is suitable for use by ISO member bodies. In the unlikely event that a problem relating to it is found, please inform the Central Secretariat at the address given below.



**COPYRIGHT PROTECTED DOCUMENT**

© ISO 2010

All rights reserved. Unless otherwise specified, no part of this publication may be reproduced or utilized in any form or by any means, electronic or mechanical, including photocopying and microfilm, without permission in writing from either ISO at the address below or ISO's member body in the country of the requester.

ISO copyright office  
Case postale 56 • CH-1211 Geneva 20  
Tel + 41 22 749 01 11  
Fax + 41 22 749 09 47  
E-mail [copyright@iso.org](mailto:copyright@iso.org)  
Web [www.iso.org](http://www.iso.org)

Published in Switzerland

## Contents

Page

Foreword .....	iv
Introduction.....	v
1 Scope .....	1
2 Normative references .....	1
3 Terms and definitions .....	2
4 Symbols.....	2
5 Inspection and testing .....	3
6 Materials .....	4
7 Design.....	7
8 Construction and workmanship .....	11
9 Type approval procedure.....	13
10 Batch tests .....	15
11 Tests/examinations on every cylinder .....	24
12 Certification.....	25
13 Marking.....	25
Annex A (informative) Description and evaluation of manufacturing imperfections and conditions for rejection of seamless steel gas cylinders at time of final inspection by the manufacturer.....	26
Annex B (normative) Ultrasonic examination .....	32
Annex C (informative) Type approval certificate .....	38
Annex D (informative) Acceptance certificate.....	39
Bibliography .....	41

## Foreword

ISO (the International Organization for Standardization) is a worldwide federation of national standards bodies (ISO member bodies). The work of preparing International Standards is normally carried out through ISO technical committees. Each member body interested in a subject for which a technical committee has been established has the right to be represented on that committee. International organizations, governmental and non-governmental, in liaison with ISO, also take part in the work. ISO collaborates closely with the International Electrotechnical Commission (IEC) on all matters of electrotechnical standardization.

International Standards are drafted in accordance with the rules given in the ISO/IEC Directives, Part 2.

The main task of technical committees is to prepare International Standards. Draft International Standards adopted by the technical committees are circulated to the member bodies for voting. Publication as an International Standard requires approval by at least 75 % of the member bodies casting a vote.

Attention is drawn to the possibility that some of the elements of this document may be the subject of patent rights. ISO shall not be held responsible for identifying any or all such patent rights.

ISO 9809-1 was prepared by Technical Committee ISO/TC 58, *Gas cylinders*, Subcommittee SC 3, *Cylinder design*.

This second edition cancels and replaces the first edition (ISO 9809-1:1999), which has been technically revised by the following:

- a) the reduction of maximum sulfur content in 6.2.2 from 0,020 % to 0,010 %, which is now applicable to all strength levels;
- b) the note in 7.3 regarding limitation of the *F* factor was deleted (as required by the United Nations *Recommendations on the Transport of Dangerous Goods: Model Regulations*);
- c) the modification of provisions for ultrasonic examination in 8.4 to include ultrasonic examination on the cylindrical area to be closed, prior to the forming process;
- d) the addition of the requirement of a base check according to 9.2.3 for all cylinder types during prototype testing;
- e) the addition of the requirement of a base check according to 9.2.3 for cylinders made from continuously cast billet material during batch testing.

ISO 9809 consists of the following parts, under the general title *Gas cylinders — Refillable seamless steel gas cylinders — Design, construction and testing*:

- *Part 1: Quenched and tempered steel cylinders with tensile strength less than 1 100 MPa*
- *Part 2: Quenched and tempered steel cylinders with tensile strength greater than or equal to 1 100 MPa*
- *Part 3: Normalized steel cylinders*

Stainless steel cylinders with tensile strength of less than 1 100 MPa will form the subject of a Part 4.



## Introduction

This part of ISO 9809 provides a specification for the design, manufacture, inspection and testing of a seamless steel cylinder for worldwide usage. The objective is to balance design and economic efficiency against international acceptance and universal utility.

ISO 9809 (all parts) aims to eliminate existing concerns about climate, duplicate inspections and restrictions because of a lack of definitive International Standards. This part of ISO 9809 should not be construed as reflecting on the suitability of the practice of any nation or region.

This part of ISO 9809 addresses the general requirements on design, construction and initial inspection and testing of pressure receptacles of the United Nations *Recommendations on the Transport of Dangerous Goods: Model Regulations*.

It is intended to be used under a variety of regulatory regimes, but is suitable for use with the conformity assessment system in 6.2.2.5 of the above-mentioned Model Regulations.

มอก. 359 เล่ม 1-2559

# Gas cylinders — Refillable seamless steel gas cylinders — Design, construction and testing —

## Part 1:

## Quenched and tempered steel cylinders with tensile strength less than 1 100 MPa

### 1 Scope

This part of ISO 9809 specifies minimum requirements for the material, design, construction and workmanship, manufacturing processes, examination and testing at manufacture of refillable quenched and tempered seamless steel gas cylinders of water capacities from 0,5 l up to and including 150 l for compressed, liquefied and dissolved gases. This part of ISO 9809 is applicable to cylinders with a maximum actual tensile strength  $R_{ma}$  of less than 1 100 MPa.

NOTE 1 If desired, cylinders of water capacity less than 0,5 l and between 150 l and 500 l can be manufactured and certified to be in compliance with this part of ISO 9809.

NOTE 2 For quenched and tempered steel cylinders with maximum tensile strength greater than or equal to 1 100 MPa, see ISO 9809-2. For normalized steel cylinders, see ISO 9809-3.

### 2 Normative references

The following referenced documents are indispensable for the application of this document. For dated references, only the edition cited applies. For undated references, the latest edition of the referenced document (including any amendments) applies.

ISO 148-1, *Metallic materials — Charpy pendulum impact test — Part 1: Test method*

ISO 6506-1, *Metallic materials — Brinell hardness test — Part 1: Test method*

ISO 6508-1, *Metallic materials — Rockwell hardness test — Part 1: Test method (scales A, B, C, D, E, F, G, H, K, N, T)*

ISO 6892-1, *Metallic materials — Tensile testing — Part 1: Method of test at room temperature*

ISO 7438, *Metallic materials — Bend test*

ISO 9329-1, *Seamless steel tubes for pressure purposes — Technical delivery conditions — Part 1: Unalloyed steels with specified room temperature properties*

ISO 9712, *Non-destructive testing — Qualification and certification of personnel*

ISO 11114-1, *Transportable gas cylinders — Compatibility of cylinder and valve materials with gas contents — Part 1: Metallic materials*

ISO 11114-4, *Transportable gas cylinders — Compatibility of cylinder and valve materials with gas contents — Part 4: Test methods for selecting metallic materials resistant to hydrogen embrittlement*

ISO 13769, *Gas cylinders — Stamp marking*

### 3 Terms and definitions

For the purposes of this document, the following terms and definitions apply.

#### 3.1

##### **batch**

quantity of up to 200 cylinders plus cylinders for destructive testing of the same nominal diameter, thickness, length and design made successively on the same equipment, from the same cast of steel and subjected to the same heat treatment for the same duration of time

#### 3.2

##### **burst pressure**

$p_b$

highest pressure reached in a cylinder during a burst test

#### 3.3

##### **design stress factor**

$F$

ratio of equivalent wall stress at test pressure,  $p_h$ , to guaranteed minimum yield strength,  $R_{eg}$

#### 3.4

##### **quenching**

hardening heat treatment in which a cylinder, which has been heated to a uniform temperature above the upper critical point,  $Ac_3$ , of the steel, is cooled rapidly in a suitable medium

#### 3.5

##### **tempering**

toughening heat treatment which follows quenching, in which the cylinder is heated to a uniform temperature below the lower critical point,  $Ac_1$ , of the steel

#### 3.6

##### **test pressure**

$p_h$

required pressure applied during a pressure test

NOTE It is used for cylinder wall thickness calculation.

#### 3.7

##### **working pressure**

settled pressure of a compressed gas at a uniform reference temperature of 15 °C in a full gas cylinder

#### 3.8

##### **yield strength**

stress value corresponding to the upper yield strength,  $R_{eH}$ , or for steels which do not exhibit a defined yield, the 0,2 % proof strength (non-proportional extension),  $R_{p0,2}$

See ISO 6892-1.

### 4 Symbols

- $a$  Calculated minimum thickness, in millimetres, of the cylindrical shell
- $a'$  Guaranteed minimum thickness, in millimetres, of the cylindrical shell
- $a_1$  Guaranteed minimum thickness, in millimetres, of a concave base at the knuckle (see Figure 2)

$a_2$	Guaranteed minimum thickness, in millimetres, at the centre of a concave base (see Figure 2)
$A$	Percentage elongation after fracture
$b$	Guaranteed minimum thickness, in millimetres, at the centre of a convex base (see Figure 1)
$c$	Maximum permissible deviation of burst profile, in millimetres (see Figures 10 and 11)
$D$	Nominal outside diameter of the cylinder, in millimetres (see Figure 1)
$D_f$	Diameter, in millimetres, of former (see Figure 6)
$F$	Design stress factor (variable) (see 3.3)
$h$	Outside depth (concave base end), in millimetres (see Figure 2)
$H$	Outside height, in millimetres, of domed part (convex head or base end) (see Figure 1)
$L_0$	Original gauge length, in millimetres, as defined in ISO 6892-1 (see Figure 5)
$N$	Ratio of the diameter of the bend test former to actual thickness of test piece, $t$
$p_b$	Measured burst pressure, in bars <sup>1)</sup> , above atmospheric pressure
$P_h$	Hydraulic test pressure, in bars, above atmospheric pressure
$P_y$	Observed pressure when cylinder starts yielding during hydraulic burst test, in bars, above atmospheric pressure
$r$	Inside knuckle radius, in millimetres (see Figures 1 and 2)
$R_{eg}$	Minimum guaranteed value of the yield strength (see 7.1.1), in megapascals, for the finished cylinder
$R_{ea}$	Actual value of the yield strength, in megapascals, as determined by the tensile test (see 10.2)
$R_{mg}$	Minimum guaranteed value of the tensile strength, in megapascals, for the finished cylinder
$R_{ma}$	Actual value of tensile strength, in megapascals, as determined by the tensile test (see 10.2)
$S_0$	Original cross-sectional area of tensile test piece, in square millimetres, in accordance with ISO 6892-1
$t$	Actual thickness of the test specimen, in millimetres
$t_m$	average cylinder wall thickness at position of testing during the flattening test, in millimetres
$u$	Ratio of distance between knife edges or platens in the flattening test to average cylinder wall thickness at the position of test
$V$	Water capacity of cylinder, in litres
$w$	Width, in millimetres, of the tensile test piece (see Figure 5)

## 5 Inspection and testing

NOTE Evaluation of conformity can be carried out according to the regulations recognized by the country(ies) in which the cylinders are intended to be used.

---

1) 1 bar =  $10^5$  Pa =  $10^5$  N/m<sup>2</sup>.

To ensure that the cylinders conform to this part of ISO 9809, they shall be subject to inspection and testing in accordance with Clauses 9, 10 and 11 by an inspection body (hereinafter referred to as "the inspector") authorized to do so.

Equipment used for measurement, testing and examination during production shall be maintained and calibrated within a documented quality management system.

## 6 Materials

### 6.1 General requirements

6.1.1 Materials for the manufacture of gas cylinders shall fall within one of the following categories:

- a) internationally recognized cylinder steels;
- b) nationally recognized cylinder steels;
- c) new cylinder steels resulting from technical progress.

For all categories, the relevant conditions specified in 6.2 and 6.3 shall be satisfied.

6.1.2 The material used for the manufacture of gas cylinders shall be steel, other than rimming quality, with non-ageing properties, and shall be fully killed with aluminium and/or silicon.

In cases where examination of this non-ageing property is required by the customer, the criteria by which it is to be specified should be agreed with the customer and inserted in the order.

6.1.3 The cylinder manufacturer shall establish means to identify the cylinders with the cast of steel from which they are made.

6.1.4 Grades of steel used for cylinder manufacture shall be compatible with the intended gas service, e.g. corrosive gases and embrittling gases (see ISO 11114-1).

6.1.5 Wherever continuously cast billet material is used, the manufacturer shall ensure that there are no deleterious imperfections (porosity) in the material to be used for making cylinders (see 9.2.3).

### 6.2 Controls on chemical composition

6.2.1 The chemical composition of all steels shall be defined at least by:

- the carbon, manganese and silicon contents in all cases;
- the chromium, nickel and molybdenum contents or other alloying elements intentionally added to the steel;
- the maximum sulfur and phosphorus contents in all cases.

The carbon, manganese and silicon contents and, where appropriate, the chromium, nickel and molybdenum contents shall be given, with tolerances, such that the differences between the maximum and minimum values of the cast do not exceed the values shown in Table 1.

The combined content of the following elements: vanadium, niobium, titanium, boron and zirconium shall not exceed 0,15 %.

The actual content of any element deliberately added shall be reported and their maximum content shall be representative of good steel making practice.

**Table 1 — Chemical composition tolerances**

Element	Maximum content (mass fraction) %	Permissible range (mass fraction) %
Carbon	< 0,30 %	0,06
	≥ 0,30 %	0,07
Manganese	All values	0,30
Silicon	All values	0,30
Chromium	< 1,50 %	0,30
	≥ 1,50 %	0,50
Nickel	All values	0,40
Molybdenum	All values	0,15

**6.2.2** Sulfur and phosphorus in the cast analysis of material used for the manufacture of gas cylinders shall not exceed the values shown in Table 2.

**Table 2 — Maximum sulfur and phosphorus limits in % (mass fraction)**

Sulfur	0,010
Phosphorus	0,020
Sulfur and phosphorus	0,025

**6.2.3** The cylinder manufacturer shall obtain and make available certificates of cast (heat) analyses of the steels supplied for the construction of gas cylinders.

Should check analyses be required, they shall be carried out either on specimens taken during manufacture from the material in the form as supplied by the steel maker to the cylinder manufacturer or from finished cylinders. In any check analysis, the maximum permissible deviation from the limits specified for the cast analyses shall conform to the values specified in ISO 9329-1.

### 6.3 Typical steels

Two typical internationally recognized steel types which have provided safe performance over many years are:

- a) chromium molybdenum steel (quenched and tempered);
- b) carbon manganese steel (quenched and tempered).

The chemical compositions of these steels, subject to the controls specified in 6.2.1, are given in Table 3.

**Table 3 — Internationally recognized steel compositions (mass fraction)**

Element	Steel grade and conditions	
	CrMo (Q and T) %	CMn (Q and T) %
Carbon	0,25 to 0,38	0,38 max.
Silicon	0,10 to 0,40	0,1 to 0,35
Manganese	0,40 to 1,00	1,35 to 1,75
Phosphorus	0,020 max.	0,020 max.
Sulfur	0,020 max.	0,020 max.
Chromium	0,8 to 1,20	
Molybdenum	0,15 to 0,40	
The actual range for each element shall be in accordance with 6.2.1 and 6.2.2 and good steel making practice. In particular, the limits specified in Table 2 take precedence over the ranges given in this table.		

## 6.4 Heat treatment

**6.4.1** The cylinder manufacturer shall certify the heat treatment process applied to the finished cylinders.

**6.4.2** Quenching in media other than mineral oil is permissible provided that:

- the method produces cylinders free of cracks.
- the manufacturer ensures that the rate of cooling does not produce any cracks in the cylinder.
- every production cylinder is subjected to a method of non-destructive testing to prove freedom from cracks, if the average rate of cooling in the medium is greater than 80 % of that in water at 20 °C without additives.
- during the production of cylinders, the concentration of the quenchant is checked and recorded during every shift to ensure that the limits are maintained. Further documented checks shall be carried out to ensure that the chemical properties of the quenchant are not degraded.

**6.4.3** The tempering process shall achieve the required mechanical properties.

The actual temperature to which a type of steel is subjected for a given tensile strength shall not deviate by more than 30 °C from the temperature specified by the cylinder manufacturer.

## 6.5 Failure to meet test requirements

In the event of failure to meet the test requirements, retesting or reheat treatment and retesting shall be carried out as follows to the satisfaction of the inspector.

- a) If there is evidence of a fault in carrying out a test or an error of measurement, a further test shall be performed. If the result of this test is satisfactory, the first test shall be ignored.
- b) If the test has been carried out in a satisfactory manner, the cause of test failure shall be identified.
  - 1) If the failure is considered to be due to the heat treatment applied, the manufacturer may subject all the cylinders implicated by the failure to a further heat treatment, e.g. if the failure is in a test representing the prototype or batch cylinders. Test failure shall require reheat treatment of all the represented cylinders prior to retesting.



This reheat treatment shall consist of either re-tempering or complete reheat treatment.

Whenever cylinders are reheat treated, the minimum guaranteed wall thickness shall be maintained.

Only the relevant prototype or batch tests needed to prove the acceptability of the new batch shall be performed again. If one or more tests prove even partially unsatisfactory, all cylinders of the batch shall be rejected.

- 2) If the failure is due to a cause other than the heat treatment applied, all cylinders with imperfections shall be either rejected or repaired such that the repaired cylinders pass the test(s) required for the repair. They shall then be re-instated as part of the original batch.

## 7 Design

### 7.1 General requirements

**7.1.1** The calculation of the wall thickness of the pressure-containing parts shall be related to the guaranteed minimum yield strength,  $R_{eg}$ , of the material in the finished cylinder.

**7.1.2** Cylinders may be designed with one or two openings along the central cylinder axis only.

**7.1.3** For calculation purposes, the value of  $R_{eg}$  shall not exceed 0,90  $R_{mg}$ .

**7.1.4** The internal pressure upon which the calculation of wall thickness is based shall be the hydraulic test pressure  $p_h$ .

### 7.2 Limitation on tensile strength

**7.2.1** Where there is no risk of hydrogen embrittlement, the maximum value of the tensile strength is limited by the ability of the steel to meet the requirements of Clauses 9 and 10, but the maximum actual tensile strength,  $R_{ma}$ , shall always be less than 1 100 MPa for chrome-molybdenum steels and in no case exceed 1 030 MPa for carbon manganese steels.

**7.2.2** Where there is a risk of hydrogen embrittlement (see ISO 11114-1), the maximum value of the tensile strength, as determined in 10.2, shall either be 880 MPa or, where the ratio  $R_{ea}/R_{ma}$  does not exceed 0,9, be 950 MPa. Alternatively, the maximum tensile strength shall be established using data derived from the tests carried out in accordance with ISO 11114-4.

**7.2.3** Other gas/material compatibility risks, including stress corrosion and hydrogen embrittlement mechanism by gases other than hydrogen, shall be assessed in accordance with ISO 11114-1 and ISO 11114-4.

### 7.3 Calculation of cylindrical shell thickness

The guaranteed minimum thickness of the cylindrical shell,  $a'$ , shall not be less than the thickness calculated using Equations (1) and (2), and additionally, condition (3) shall be satisfied.

$$a = \frac{D}{2} \left( 1 - \sqrt{\frac{10 F R_{eg} - \sqrt{3} P_h}{10 F R_{eg}}} \right) \quad (1)$$

where the value of  $F$  is the lesser of  $\frac{0,65}{R_{eg}/R_{mg}}$  or 0,85.

$R_{eg}/R_{mg}$  shall not exceed 0,90.

The wall thickness shall also satisfy Equation (2):

$$a \geq \frac{D}{250} + 1 \quad (2)$$

with an absolute minimum of  $a = 1,5$  mm.

The burst ratio shall be satisfied by test as given in Equation (3):

$$p_b/p_h \geq 1,6 \quad (3)$$

NOTE It is generally assumed that  $p_h = 1,5$  times working pressure for compressed gases for cylinders designed and manufactured to conform with this part of ISO 9809.

#### 7.4 Calculation of convex ends (heads and bases)

**7.4.1** The thickness,  $b$ , at the centre of a convex end shall be not less than that required by the following criteria: where the inside knuckle radius,  $r$ , is not less than  $0,075D$  then:

$$b \geq 1,5 a \text{ for } 0,40 > H/D \geq 0,20;$$


$$b \geq a \text{ for } H/D \geq 0,40.$$

To obtain a satisfactory stress distribution in the region where the end joins the shell, any thickening of the end that may be required shall be gradual from the point of juncture, particularly at the base. For the application of this rule, the point of juncture between the shell and the end is defined by the horizontal lines indicating dimension  $H$  in Figure 1.

Shape b) shall not be excluded from this requirement.

**7.4.2** The cylinder manufacturer shall prove by the pressure cycling test detailed in 9.2.2 that the design is satisfactory.

The shapes shown in Figure 1 are typical of convex heads and base ends. Shapes a), b), d) and e) are base ends and shapes c) and f) are heads.



**Key**

1 cylindrical part

**Figure 1 — Typical convex ends**

## 7.5 Calculation of concave base ends

When concave base ends (see Figure 2) are used, the following design values are recommended:

$$a_1 \geq 2a$$

$$a_2 \geq 2a$$

$$h \geq 0,12D$$

$$r \geq 0,075D$$

The design drawing shall at least show values for  $a_1$ ,  $a_2$ ,  $h$  and  $r$ .

To obtain a satisfactory stress distribution, the thickness of the cylinder shall increase progressively in the transition region between the cylindrical part and the base.

The cylinder manufacturer shall in any case prove by the pressure cycling test detailed in 9.2.2 that the design is satisfactory.




Figure 2 — Concave base end

## 7.6 Neck design

**7.6.1** The external diameter and thickness of the formed neck end of the cylinder shall be adequate for the torque applied in fitting the valve to the cylinder. The torque may vary according to the diameter of thread, the form of thread and the sealant used in the fitting of the valve.

NOTE For information on torques, see ISO 13341.

**7.6.2** In establishing the minimum thickness, consideration shall be given to obtaining a thickness of wall in the cylinder neck which will prevent permanent expansion of the neck during the initial and subsequent fittings of the valve into the cylinder without support of an attachment. The external diameter and thickness of the formed neck end of the cylinder shall not be damaged (no permanent expansion or crack) by the application of the maximum torque required to fit the valve to the cylinder (see ISO 13341) and the stresses when the cylinder is subjected to its test pressure. In specific cases (e.g. very thin walled cylinders), where these stresses cannot be supported by the neck itself, the neck may be designed to require reinforcement, such as a neck ring or shrunk on collar, provided the reinforcement material and dimensions are clearly specified by the manufacturer and this configuration is part of the type approval procedure.

### 7.7 Foot rings

When a foot ring is provided, it shall be sufficiently strong and made of material compatible with that of the cylinder. The shape should preferably be cylindrical and shall give the cylinder sufficient stability. The foot ring shall be secured to the cylinder by a method other than welding, brazing or soldering. Any gaps which may form water traps shall be sealed by a method other than welding, brazing or soldering.

### 7.8 Neck rings

When a neck ring is provided, it shall be sufficiently strong and made of material compatible with that of the cylinder and shall be securely attached by a method other than welding, brazing or soldering.

The manufacturer shall ensure that the axial load to remove the neck-ring is greater than 10 times the weight of the empty cylinder, but not less than 1 000 N and that the torque to turn the neck ring is greater than 100 Nm.

### 7.9 Design drawing

A fully dimensioned drawing shall be prepared, which includes the specification of the material and details relevant to the design of the permanent fittings. Dimensions of non-safety related fittings can be agreed on between the customer and manufacturer and need not be shown on the design drawing.

## 8 Construction and workmanship

### 8.1 General

The cylinder shall be produced by

- a) forging or drop forging from a solid ingot or billet, or
- b) manufacturing from seamless tube, or
- c) pressing from a flat plate.

Metal shall not be added in the process of closure of the end. Manufacturing defects shall not be corrected by the plugging of bases.

### 8.2 Wall thickness

During production, each cylinder or semi-finished shell shall be examined for thickness. The wall thickness at any point shall be not less than the minimum thickness specified.

### 8.3 Surface imperfections

The internal and external surfaces of the finished cylinder shall be free from imperfections which could adversely affect the safe working of the cylinder.

NOTE For examples of imperfections and assistance on their evaluation, see Annex A.

### 8.4 Ultrasonic examination

**8.4.1** After completion of the final heat treatment and after the final cylindrical wall thickness has been achieved, each cylinder shall be ultrasonically examined for internal, external and sub-surface imperfections in accordance with Annex B.

For small completed cylinders with a cylindrical length of less than 200 mm or where the product of  $p_h \times V < 600$  (for  $R_{ma} \geq 650$  MPa) or  $p_h \times V < 1\,200$  (for  $R_{ma} < 650$  MPa), the ultrasonic examination is not necessary.

**8.4.2** Regardless of the size of the cylinder, in addition to the ultrasonic examination as specified in 8.4.1, the cylindrical area to be closed (which creates the shoulder and, in case of cylinders made from tube, also the base) shall be ultrasonically examined prior to the forming process to detect any defects that after closure could be positioned in the cylinder ends.

NOTE This examination does not necessarily cover the tests required in 6.4.2.

## **8.5 Out-of-roundness**

The out-of-roundness of the cylindrical shell, i.e. the difference between the maximum and minimum outside diameters at the same cross-section, shall not exceed 2 % of the mean of these diameters.

## **8.6 Mean diameter**

The mean external diameter of the cylindrical part outside the transition zones on a cross-section shall not deviate by more than  $\pm 1$  % from the nominal design diameter.

## **8.7 Straightness**

The maximum deviation of the cylindrical part of the shell from a straight line shall not exceed 3 mm/m length (see Figure 3).

## **8.8 Verticality and stability**


For a cylinder designed to stand on its base, the deviation from vertical shall not exceed 10 mm/m length (see Figure 3) and the outer diameter of the surface in contact with the ground is recommended to be greater than 75 % of the nominal outside diameter.

## **8.9 Neck threads**

The internal neck threads shall conform to a recognized standard agreed between the parties to permit the use of a corresponding valve thus minimizing neck stresses following the valve torquing operation. Internal neck threads shall be checked using gauges corresponding to the agreed neck thread or by an alternative method agreed on between the parties.

NOTE For example, where the neck thread is specified to be in accordance with ISO 11116-1, the corresponding gauges are specified in ISO 11116-2.

Particular care shall be taken to ensure that neck threads are accurately cut, are of full form and free from any sharp profiles, e.g. burrs.



**Key**

- a maximum  $0,01 \times l$  (see 8.8)
- b maximum  $0,003 \times l$  (see 8.7)

**Figure 3 — Illustration of deviation of cylindrical part of shell from a straight line and from vertical**

## 9 Type approval procedure

### 9.1 General requirements

A technical specification of each new design of cylinder or cylinder family as defined in f), including design drawing, design calculations, steel details, manufacturing process and heat treatment details, shall be submitted by the manufacturer to the inspector. The type approval tests detailed in 9.2 shall be carried out on each new design under the supervision of the inspector.

A cylinder shall be considered to be of a new design, compared with an existing approved design, when at least one of the following applies:

- a) it is manufactured in a different factory;
- b) it is manufactured by a different process (see 8.1); this includes the case when major process changes are made during the production period, e.g. end forging to spinning and change in the heat treatment process;
- c) it is manufactured from a steel of different specified chemical composition range from that defined in 6.2.1;
- d) it is given a different heat treatment beyond the limits stipulated in 6.4;
- e) the base or the base profile has changed, e.g. concave, convex, hemispherical, or also if there is a change in base thickness/cylinder diameter ratio;
- f) the overall length of the cylinder has increased by more than 50 % (cylinders with a length/diameter ratio less than 3 shall not be used as reference cylinders for any new design with this ratio greater than 3);

- g) the nominal outside diameter has changed;
- h) the guaranteed minimum thickness has changed;
- i) the hydraulic test pressure,  $p_h$ , has been increased (where a cylinder is to be used for lower-pressure duty than that for which design approval has been given, it shall not be deemed to be a new design);
- j) the guaranteed minimum yield strength,  $R_{eg}$  and/or the guaranteed minimum tensile strength,  $R_{mg}$ , for the finished cylinder have changed.

## 9.2 Prototype tests

### 9.2.1 General requirements

A minimum of 50 cylinders, which are guaranteed by the manufacturer to be representative of the new design, shall be made available for prototype testing. However, if for special applications the total number of cylinders required is less than 50, a sufficient number of cylinders shall be made to complete the prototype tests required, in addition to the production quantity, but in this case, the approval validity is limited to this particular production batch.

In the course of the type approval process, the inspector shall select the necessary cylinders for testing and

- a) verify that:
  - the design conforms to the requirements of Clause 7;
  - the thicknesses of the walls and ends on two cylinders (those taken for mechanical testing) meet the requirements of 7.3 to 7.6, the measurements being taken at least at three transverse sections of the cylindrical part and on a longitudinal section of the base and head;
  - the requirements of Clause 6 are complied with;
  - the requirements of 7.6, 7.7, 7.8 and 8.5 to 8.9 inclusive are complied with for all cylinders selected for inspection;
  - the internal and external surfaces of the cylinders are free of any defect which might make them unsafe to use (for examples, see Annex A).
- b) supervise the following tests on the cylinders selected:
  - the tests specified in 10.1.2 a) (hydraulic burst test) on two cylinders, the cylinders bearing representative stamp markings;
  - the tests specified in 10.1.2 b) (mechanical testing) on two cylinders, the test pieces being identifiable with the batch;
  - the tests specified in 9.2.3 (base check) on the two cylinders selected for mechanical testing;
  - the tests specified in 9.2.2 (pressure cycling test) on three cylinders, the cylinders bearing representative stamp markings;
  - the geometrical requirements for the neck thread are complied with for all cylinders selected for inspection.



### 9.2.2 Pressure cycling test

This test shall be carried out on cylinders bearing representative markings with a non-corrosive liquid subjecting the cylinders to successive reversals at an upper cyclic pressure, which is equal to the hydraulic test pressure,  $p_h$ . The cylinders shall withstand 12 000 cycles without failure.

For cylinders with a hydraulic test pressure  $p_h > 450$  bar, the upper cyclic pressure may be reduced to two thirds of this test pressure. In this case, the cylinders shall withstand 80 000 cycles without failure.

The value of the lower cyclic pressure shall not exceed 10 % of the upper cyclic pressure, but shall have an absolute maximum of 30 bar.

The cylinder shall actually experience the maximum and minimum cyclic pressures during the test.

The frequency of reversals of pressure shall not exceed 0,25 Hz (15 cycles/min.). The temperature measured on the outside surface of the cylinder shall not exceed 50 °C during the test.

After the test, the cylinder bases shall be sectioned to measure the thickness and to ensure that this thickness is sufficiently close to the minimum thickness prescribed in the design and shall be within the usual production tolerances. In no case shall the actual base thickness exceed the minimum value(s) specified on the drawings by more than 15 %.

The test shall be considered satisfactory if the cylinder attains the required number of cycles without developing a leak.

### 9.2.3 Base check

A meridian section shall be made in the base centre of the cylinder and one of the surfaces thus obtained polished for examination under a magnification of between  $\times 5$  and  $\times 10$ .

The cylinder shall be regarded as defective if the presence of cracks is detected. It shall also be regarded as defective if the dimensions of any pores or inclusions present reach values considered to pose a threat to safety.

In cases where the base is suspected to be plugged, the section shall be etched after the first examination to verify the absence of a plug. Plugged cylinders shall not be approved.

In no case shall the sound thickness (i.e. the thickness with no imperfections) in the base centre be less than the minimum specified thickness (see 7.4.1).

## 9.3 Type approval certificate

If the results of the checks according to 9.2 are satisfactory, the inspector shall issue a type approval certificate. Annex C provides a typical example of a suitable form of type approval certificate. Other formats with at least the same content are also acceptable.

## 10 Batch tests

### 10.1 General requirements

10.1.1 All tests for checking the quality of the gas cylinder shall be carried out at the completion of cylinder manufacture, i.e. at any stage after the heat treatment.

For the purposes of batch testing, the manufacturer shall provide the inspector with:

— the type approval certificate;

- the certificates stating the cast analysis of the steel supplied for the manufacture of the cylinders;
- evidence that appropriate heat treatment has been performed;
- the certificates showing the ultrasonic examination results;
- a list of the cylinders, stating serial numbers and stamp markings, as required;
- confirmation that threads have been checked in accordance with gauging requirements. The gauges to be used shall be specified (e.g. ISO 11191).


**10.1.2** During batch testing, the inspector shall undertake the following.

- Ascertain that the type approval certificate has been obtained and that the cylinders conform to it.
- Check whether the requirements given in Clauses 6, 7 and 8 have been met and, in particular, check by an external and internal visual examination of the cylinders whether their construction is satisfactory. The inspector shall verify that the requirements of 7.7, 7.8 and 8.2 to 8.9 have been fulfilled by the manufacturer. The visual examination shall cover at least 10 % of the cylinders submitted. However, if an unacceptable imperfection is found (for examples, see Annex A), 100 % of cylinders shall be visually inspected.
- Select the necessary cylinders per batch for destructive testing and carry out the tests specified in 10.1.2a) (hydraulic burst tests) and 10.1.2b) (mechanical testing). Where alternative tests are permitted, the purchaser and manufacturer shall agree on which tests are to be carried out.
- Check whether the information supplied by the manufacturer referred to in 10.1.1 is correct; random checks shall be carried out.
- Assess the results of hardness testing specified in 11.3.

The following tests shall be carried out on each batch of cylinders.

- a) On one cylinder, one hydraulic burst test (see 10.5).
- b) On a further cylinder:
  - one tensile test in the longitudinal direction (see 10.2);
  - either two bend tests (see 10.3.1) in a circumferential direction, one flattening test (see 10.3.2) or one ring flattening test (see 10.3.3);
  - when the thickness of the cylinder permits the machining of a test piece at least 3 mm thick, three impact tests in the transverse or longitudinal direction as required in 10.4;
  - for cylinders made from continuously cast billet material, a base check in accordance with 9.2.3.

NOTE For the location of test pieces, see Figure 4.



**Key**

- 1 bend test pieces or flattening ring
- 2 transverse impact pieces
- 3 longitudinal impact test piece (alternative positions shown dashed)
- 4 tensile test pieces

**Figure 4 — Typical location of test pieces**

## 10.2 Tensile test


**10.2.1** A tensile test shall be carried out on material taken from the cylindrical part of the cylinder by adopting either of the following procedures.

- a) Rectangular specimens shall be prepared in accordance with Figure 5 and with a gauge length  $L_0 = 5,65 \sqrt{S_0}$ . The two faces of the test piece, representing the inside and outside surfaces of the cylinder, shall not be machined. The elongation after fracture,  $A$ , measured shall be not less than 14 %.
- b) Machined round specimens shall be prepared having the maximum diameter practicable, the elongation,  $A$ , measured on a gauge length of five times the specimen diameter being no less than 16 %.

It is recommended that machined round specimens not be used for wall thickness less than 3 mm.

**10.2.2** The tensile test shall be carried out in accordance with ISO 6892-1.

**NOTE** Attention is drawn to the method of measurement of elongation described in ISO 6892-1, particularly in cases where the tensile test piece is tapered, resulting in a point of fracture away from the middle of the gauge length.



$$w \leq 4t$$

$$w < D/8$$

Figure 5 — Tensile test piece

### 10.3 Bend test and flattening test

#### 10.3.1 Bend test




Figure 6 — Illustration of bend test

**10.3.1.1** The bend test shall be carried out in accordance with ISO 7438 on two test pieces obtained by cutting either one or two rings of width 25 mm or  $4t$ , whichever is the greater, into equal parts. Each test piece shall be of sufficient length to permit the bend test to be carried out correctly. Only the edges of each strip may be machined.

**10.3.1.2** The test piece shall not crack when bent inwards around the former until the inside surfaces are not further apart than the diameter of the former (see Figure 6).

**10.3.1.3** The diameter of the former,  $D_f$ , shall be established from Table 4.

For the actual tensile strength,  $R_{ma}$ , given in Table 4;  $D_f \leq n \times$  test piece thickness,  $t$ .

### 10.3.2 Flattening test

**10.3.2.1** The flattening test shall be performed on one cylinder selected from each batch after heat treatment.

**10.3.2.2** The test cylinder shall be flattened between wedge-shaped knife edges with a 60° included angle, the edges being rounded to a nominal radius of 13 mm. The length of the wedges shall be not less than the width of the flattened cylinder. The longitudinal axis of the cylinder shall be at an angle of approximately 90° to the knife edges.

**10.3.2.3** The test cylinder shall be flattened until the distance between the knife edges is in accordance with Table 4. The flattened cylinder shall remain visually uncracked.

**Table 4 — Bend test and flattening test requirements**

Actual tensile strength, $R_{ma}$ MPa	Bend test Value of $n$	Flattening test (cylinder or ring) Value of $u^a$
$R_{ma} \leq 800$	4	6
$800 < R_{ma} \leq 880$	5	7
$880 < R_{ma} \leq 950$	6	8
$950 < R_{ma} < 1\ 100$	7	9
<sup>a</sup> Distance between knife edges or platens = $u \times t_m$ , where $t_m$ is the average cylinder wall thickness at the position of testing.		


### 10.3.3 Ring flattening test

The ring flattening test shall be carried out on one ring of width 25 mm or 4  $t$ , whichever is the greater, taken from the cylinder body. Only the edges of the ring may be machined. The ring shall be flattened between platens until the distance between platens is in accordance with Table 4. The flattened ring shall remain visually uncracked.

## 10.4 Impact test

**10.4.1** Except for the requirements set out in this subclause, the test shall be carried out in accordance with ISO 148-1.


The impact test pieces shall be taken in the direction as required in Table 5 from the wall of the cylinder. The notch shall be perpendicular to the face of the cylinder wall (see Figure 7). For longitudinal tests, the test piece shall be machined all over (on six faces). If the wall thickness does not permit a final test piece width of 10 mm, the width shall be as near as practicable to the nominal thickness of the cylinder wall. The test pieces taken in the transverse direction shall be machined on four faces only, the outer face of the cylinder wall unmachined and the inner face optionally machined as shown in Figure 8.



**Key**

- 1 transverse test piece
- 2 cylinder longitudinal axis
- 3 Charpy V-notch perpendicular to the wall
- 4 longitudinal test piece

**Figure 7 — Description of transverse and longitudinal impact test pieces**



**Key**

- 1 machining optional
- 2 striking anvil
- 3 test piece
- 4 centre of strike
- a Direction of strike.

**Figure 8 — Description of transverse impact testing**

10.4.2 Minimum acceptance values shall be as given in Table 5.

Table 5 — Impact test acceptance values


Cylinder diameter $D$ , mm	> 140			$\leq 140$
Direction of testing	transverse			longitudinal
Width of test piece, mm	3 to 5	> 5 to 7,5	> 7,5 to 10	3 to 10
Test temperature <sup>a</sup> , °C	-50			-50
Mean of three test pieces	30	35	40	60
Impact Value <sup>b</sup> , J/cm <sup>2</sup>				
Individual test piece	24	28	32	48
<sup>a</sup> For applications at lower temperatures, the test shall be carried out at the lowest temperature specified. <sup>b</sup> The impact value (J/cm <sup>2</sup> ) is calculated by dividing the impact energy (J) by the actual cross-sectional area below the notch (cm <sup>2</sup> ) of the Charpy test specimen.				

## 10.5 Hydraulic burst test

### 10.5.1 Test installation

The test equipment shall be capable of operating in accordance with the test conditions specified in 10.5.2 and of producing accurately the information specified in 10.5.3.

A typical hydraulic burst test installation is illustrated in Figure 9.



**Key**

- 1 test fluid reservoir
- 2 tank for measurement of test fluid (the test fluid reservoir may also be used as the measuring tank)
- 3 pump
- 4 pressure gauge
- 5 pressure/time curve recorder
- 6 vent or air release valve
- 7 test well
- 8 cylinder

**Figure 9 — Typical hydraulic burst test installation**

**10.5.2 Test conditions**

As the cylinder and test equipment are being filled with water, care shall be taken to ensure that no air is trapped in the circuit by operating the hydraulic pump until water is discharged from the vent or air-release valve. During the test, pressurization shall be carried out in two successive stages.

- a) In the first stage, the pressure shall be increased at a rate of not more than 5 bar/s up to a pressure value corresponding to the initiation of plastic deformation.
- b) In the second stage, the pump discharge rate shall be maintained at as constant a level as possible until the cylinder bursts.



### 10.5.3 Interpretation of test results

10.5.3.1 Interpretation of the burst test results shall involve:

- a) examination of the pressure/time curve or pressure/volume of water used curve, to determine the pressure at which plastic deformation of the cylinder commences, together with the burst pressure;
- b) examination of the burst tear and of the shape of its edges.

10.5.3.2 For the results of a burst test to be considered satisfactory, the following requirements shall be met.

- a) The observed yield pressure,  $p_y$ , shall be equal to or greater than  $\frac{1}{F} \times$  the test pressure, i.e. Equation (4):

$$p_y \geq \frac{1}{F} \times p_h \quad (4)$$

- b) The actual burst pressure,  $p_b$ , shall be equal to or greater than 1,6 times the test pressure, i.e.  $p_b \geq 1,6 p_h$ .

10.5.3.3 The cylinder shall remain in one piece and shall not fragment.

10.5.3.4 The main fracture shall be in the cylindrical portion and shall not be brittle, i.e. the fracture edges shall be inclined with respect to the wall. The tear shall not reveal a significant defect in the metal and in no case shall reach the neck. For concave bases, the tear shall not run further than the cylindrical body at the base end and, for convex bases, the tear shall not reach the centre of the base.

10.5.3.5 For cylinders with a wall thickness of less than 7,5 mm, the fracture shall be acceptable only if it conforms to one of the following descriptions:

- a) longitudinal, without branching (see Figure 10);
- b) longitudinal, with a side branching at each end, which in no case extends beyond the longitudinal plane normal to the fracture plane (see Figure 11).

### 10.5.4 Acceptance criteria

Figure 10 and Figure 11 illustrate satisfactory burst test profiles and batches represented by such results shall be accepted.

If the configuration of the fracture does not conform to Figure 10 or Figure 11, but all other material and mechanical tests are satisfactory, investigation of the cause of the non-conformity shall be undertaken prior to acceptance or rejection of the batch.




Figure 10 — Acceptable burst profiles — longitudinal without branching




Figure 11 — Acceptable burst profiles — longitudinal with side branching

## 11 Tests/examinations on every cylinder

### 11.1 General

During production, the examinations specified in 8.2 and 8.4 shall be carried out on all cylinders.

Following final heat treatment, all cylinders, except those selected for testing under Clause 10, shall be subjected to the following tests:

- a hydraulic proof pressure test in accordance with 11.2.1 or a hydraulic volumetric expansion test in accordance with 11.2. Test method requirements are given in 11.2. Additional guidance for these test methods and equipment control (calibration and maintenance) can be found in ISO 6406. The purchaser and manufacturer shall agree on which of these alternatives shall be carried out;
- a hardness test in accordance with 11.3;
- a leak test in accordance with 11.4;
- a water capacity check in accordance with 11.5.

### 11.2 Hydraulic test

#### 11.2.1 Proof pressure test

The water pressure in the cylinder shall be increased at a controlled rate until the test pressure,  $p_h$ , is reached within a measuring tolerance of 0/+3 % or +10 bar, whichever is the lower.

The cylinder shall remain under pressure,  $p_h$ , for at least 30 s to establish that the pressure does not fall and that there are no leaks. During the period that the cylinder is under test pressure, it shall be visible (including the base) and remain dry. After the test, the cylinder shall show no visible permanent deformation and no trace of moisture implying leakage.

#### 11.2.2 Volumetric expansion test

The water pressure in the cylinder shall be increased at a controlled rate until the test pressure,  $p_h$ , is reached within a measuring tolerance of 0/+3 % or +10 bar, whichever is the lower.

The cylinder shall remain under pressure,  $p_h$ , for at least 30 s and the total volumetric expansion measured. The pressure shall then be released and the volumetric expansion re-measured.

The cylinder shall be rejected if it shows a permanent expansion (i.e. volumetric expansion after the pressure has been released) in excess of 10 % of the total volumetric expansion measured at the test pressure,  $p_h$ .

The total and permanent expansion readings shall be recorded, together with the corresponding serial number of each cylinder tested, so that the elastic expansion (i.e. total expansion less permanent expansion) under the test pressure can be established for each cylinder.

### 11.3 Hardness test

A hardness test in accordance with ISO 6506-1 (Brinell), ISO 6508-1 (Rockwell) or other equivalent methods, shall be carried out by the manufacturer. The hardness values thus determined shall be within the limits specified by the cylinder manufacturer for the material, dependent upon the heat treatment used for the production of the cylinder and the intended gas service (e.g. embrittling gases).

NOTE Methods for measuring the surface indentations other than given in ISO 6506-1 or ISO 6508-1 can be used subject to agreement between the parties concerned, provided that an equal level of accuracy can be demonstrated.

### 11.4 Leak test

The manufacturer shall employ such manufacturing techniques and apply such tests as will demonstrate to the satisfaction of the inspector that the cylinders do not leak.

For cylinders with base ends formed by spinning, the following are three examples of typical testing procedures:

- a pneumatic leakage test where the bottom end shall be clean and free from all moisture on the test pressure side. The inside area of the cylinder bottom surrounding the closure shall be subjected to a pressure equal to at least two thirds of the test pressure of the cylinder for a minimum of 1 min; this area shall be not less than 20 mm in diameter around the closure and at least 6% of the total bottom area. The opposite side shall be covered with water or another suitable medium and closely examined for indication of leakage; cylinders that leak shall be rejected;
- a low pressure pneumatic test;
- a helium leak test.

### 11.5 Capacity check

The manufacturer shall verify that the water capacity conforms to the design drawing.

## 12 Certification

Each batch of cylinders shall be covered by a certificate signed by the inspector to the effect that the cylinders meet the requirements of this part of ISO 9809 in all respects. Annex D provides a typical example of a suitably worded acceptance certificate. Other formats with at least the same content are also acceptable.

Copies of the certificate shall be issued to the manufacturer. The original certificate shall be retained by the inspector and the copies shall be retained by the manufacturer, in accordance with the regulations of the relevant statutory authority.

NOTE Attention is drawn to national regulations which might have additional or overriding requirements concerning the issuing and retention of certificates.

## 13 Marking

Each cylinder shall be permanently marked on the shoulder or on a reinforced part of the cylinder or on a permanently fixed collar or neck ring, in accordance with ISO 13769 or the relevant marking regulations of the countries of use.

NOTE Attention is drawn to requirements for marking in relevant regulations which might override the requirements given in this part of ISO 9809.

## **Annex A** (informative)

### **Description and evaluation of manufacturing imperfections and conditions for rejection of seamless steel gas cylinders at time of final inspection by the manufacturer**

#### **A.1 General**

Several types of imperfection can occur during the manufacturing of a seamless steel gas cylinder.

Such imperfections can be mechanical or material. They can be due to the basic material used, the manufacturing process, heat treatments, manipulations, necking, machining or marking operations and other circumstances during manufacture.

This annex identifies the manufacturing imperfections most commonly met and provides general information for the inspectors who perform the visual inspection. Nevertheless, extensive field experience, good judgment and independence from production are necessary for the inspector to detect and to be able to evaluate and judge an imperfection at the time of the visual inspection.

#### **A.2 General conditions of inspection**

**A.2.1** It is essential to perform the visual internal and external inspection under good conditions, as follows.

- The surface of the metal, in particular of the inner wall, should be completely clean, dry and free of oxidation products, corrosion, scale, etc., as these could obscure other more serious imperfections. Where necessary, the surface shall be cleaned under closely controlled conditions by suitable methods before further inspection.
- Appropriate sources of illumination with sufficient intensity shall be used.
- After the cylinders have been closed and the threads have been cut, the internal neck area shall be examined by means of an introscope, dental mirror or other suitable appliance.

**A.2.2** Small imperfections can be removed by local dressing, grinding, machining or other appropriate method.

Great care should be taken to avoid introducing new injurious imperfections.

After such a repair, the cylinders shall be re-examined and, if the cylindrical wall thickness is reduced, it shall be rechecked.

#### **A.3 Manufacturing imperfections**

The most commonly found manufacturing imperfections and their definitions are listed in Table A.1.

Rejection limits for repair or reject are also included in Table A.1. These rejection limits have been established following considerable field experience. They apply to all sizes and types of cylinders and service conditions. Nevertheless, some customer specifications, some types of cylinders or some special service conditions can require stronger conditions.

#### A.4 Rejected cylinders

- a) All rejected cylinders shall be rendered unserviceable for their original application.
- b) It may be possible to produce cylinders for different service conditions from rejected cylinders.

**Table A.1 — Manufacturing imperfections**

Imperfection	Description	Conditions for rejection and/or action	Repair/Reject
Bulge	Visible swelling of the wall	All cylinders with such an imperfection	Reject
Dent (flats)	A depression in the wall which has neither penetrated nor removed metal with a depth greater than 1 % of the external cylinder diameter (see Figure A.1; see also excessive grinding or machining)	— When the depth of the dent exceeds 2 % <sup>a</sup> of the external diameter of the cylinder	Reject
		— When the depth of the dent is greater than 1 mm and when the diameter of the dent is less than 30 times its depth <sup>a</sup>	Permit repair
Cut, gouge, metallic or scale impression	An impression in the wall where metal has been removed or redistributed (due basically to the introduction of foreign bodies on the mandrel or matrix during extrusion or drawing operations)	— Inside imperfection: if not superficial, with sharp notches more than 5 % of wall thickness <sup>b</sup>	Reject
		— Outside imperfection: when the depth exceeds 5 % of the wall thickness	Repair possible (see A.2.2)
Dent containing cut or gouge	A depression in the wall which contains a cut or gouge (see Figure A.2)	All cylinders with such imperfections	Reject
Excessive grinding or machining	Local reduction of wall thickness by grinding or machining	— When the wall thickness is reduced to below the minimum design thickness	Reject
		— When it results in the formation of a dent	see dent
Rib	A longitudinal raised surface with sharp corners having a height of 3% or more than the wall thickness (see Figure A.3)	— Inside imperfection: when height exceeds 5 % of wall thickness or when length exceeds 10 % of the length of the cylinders — Outside imperfection: when height exceeds 5 % of wall thickness or when length exceeds 5 times the thickness of the cylinders	Repair, if possible or reject (see A.2.2)
Groove	A longitudinal notch having a depth of 3% or more than wall thickness (see Figure A.4)	— Inside imperfection: when depth exceeds 5 % of wall thickness or when length exceeds 10 % of the length of the cylinders — Outside imperfection: when depth exceeds 5 % of wall thickness or when the length exceeds 5 times the thickness of the cylinders	Repair, if possible or reject (see A.2.2)
Lamination	Layering of the material within the cylinder wall and sometimes appearing as a discontinuity, crack lap or bulge at the surface (see Figure A.5)	— Inside imperfection: all cylinders with such imperfection	Repair, if possible, or reject
		— Outside imperfection: all cylinders with such an imperfection	Repair, if possible, or reject (see A.2.2)
Crack	Split, material separation	— When not removable within thickness tolerance	Reject
		— When removable within thickness tolerance	Repair

Table A.1 (continued)

Imperfection	Description	Conditions for rejection and/or actions	Repair/Reject
Neck cracks	Appear as lines which run vertically down the thread and across the thread faces (not to be confused with tap marks = thread machining marks; see Figure A.6)	All cylinders with such imperfections	Reject
Shoulder folds and/or shoulder cracks	Folding with peaks and troughs situated in the internal shoulder area, which can propagate into the threaded area of the shoulder (see Figure A.7) Cracks can start from folds in the internal shoulder area and propagate into the cylindrical machined or threaded area of the shoulder (see Figure A.8 for exactly where shoulder cracks start and how they propagate)	— Folds or cracks which are visible as a line of oxide running into the threaded portion shall be removed by a machining operation until the lines of oxide are no longer visible (see Figure A.7) After machining, the whole area shall be re-inspected carefully and the wall thickness verified	Repair, if possible
		— If folding or lines of oxide have not been removed by machining, if cracks are always visible or if wall thickness is unsatisfactory	Reject
		— Folds which extend beyond the machined area and are clearly visible as open depressions where no oxides have been trapped into the metal, shall be accepted provided that the peaks are smooth and the root of the depression is rounded	Acceptable
Internal cracks in base	Splits in the metal of the bottom of the cylinder in star form	— When not removable within thickness tolerance	Reject
		— When removable within thickness tolerance	Repair
"Orange peel" surface	Orange peel appearance due to discontinuous metal flow	— If sharp cracks are visible in the orange peel surface	Reject
Internal neck threads damaged or out of tolerance	Neck threads damaged, with dents, cuts, burrs or out of tolerance	— When the design permits, threads may be re-tapped and re-checked by the appropriate thread gauge and carefully visually re-examined. The appropriate number of effective threads shall be guaranteed	Repair
		— If not reparable	Reject
Pitting	Severe surface corrosion	All cylinders with such imperfections visible after shot blasting	Reject
Non-conformity with design drawing		All cylinders presenting such an imperfection	Repair if possible or Reject
Neck ring not secure	Neck ring turns under application of low torque or pulls off under low axial load (see ISO 11117)	All cylinders presenting such an imperfection	Repair possible according to approved method only
Arc or torch burns	Partial burning of the cylinder metal, the addition of weld metal or the removal of metal by scarfing or cratering	All cylinders presenting such imperfections	Reject
<p><sup>a</sup> On small diameter cylinders, these general limits may have to be adjusted. Consideration of appearance also plays a part in the evaluation of dents, especially in the case of small cylinders.</p> <p><sup>b</sup> Consideration of appearance and localization (in thicker parts with lower stresses) can be taken into account.</p>			




Figure A.1 — Dent




Figure A.2 — Dent containing cut or gouge




Figure A.3 — Rib




Figure A.4 — Groove






Figure A.5 — Lamination



**Key**

- 1 neck cracks
- 2 propagated crack in the neck

Figure A.6 — Neck cracks




**Key**

- 1 folds or cracks
- 2 after machining

Figure A.7 — Cylinder shoulder folds or cracks before and after machining





**Key**

- 1 shoulder cracks
- 2 folds
- 3 propagated crack in the shoulder

**Figure A.8 — Shoulder cracks**

## **Annex B** (normative)

### **Ultrasonic examination**

#### **B.1 General**

This annex is based on techniques used by cylinder manufacturers. Other techniques of ultrasonic examination may be used, provided these have been demonstrated to be suitable for the manufacturing method.

#### **B.2 General requirements**

The ultrasonic examination equipment shall be capable of at least detecting the reference standard notches described in B.3.2. It shall be serviced regularly in accordance with the manufacturer's operating instructions to ensure that its accuracy is maintained. Inspection records and approval certificates for the equipment shall be maintained.

The operation of the ultrasonic examination equipment shall be by qualified and experienced personnel certified at least to Level 1 and supervised by personnel certified at least to Level 2 in accordance with ISO 9712. Other standards, which meet or exceed these minimum requirements, may be used subject to approval by the inspector. The inner and outer surfaces of any cylinder, which is to be examined ultrasonically, shall be in a condition suitable for an accurate and reproducible examination.

For flaw detection, the pulse echo system shall be used. For thickness measurement, either the resonance method or the pulse echo system shall be used. Either contact or immersion techniques of examination shall be used.

A coupling method which ensures adequate transmission of ultrasonic energy between the test probe and the cylinder shall be used.

#### **B.3 Flaw detection of the cylindrical parts**


##### **B.3.1 Procedure**

The cylinders to be examined and the search unit shall have a rotating motion and translation relative to one another such that a helical scan of the cylinder will be described. The velocity of rotation and translation shall be constant to within  $\pm 10\%$ . The pitch of the helix shall be less than the width covered by the probe (at least a 10 % overlap shall be guaranteed) and be related to the effective beam width such as to ensure 100 % coverage at the velocity of rotational and translation used during the calibration procedure.

An alternative scanning method may be used for transverse detection of imperfections, in which the scanning or relative movement of the probes and the work piece is longitudinal, the sweeping motion being such as to ensure a 100 % surface coverage with approximately 10 % overlapping of the sweeps.

The cylinder wall shall be examined for longitudinal imperfections with the ultrasonic energy transmitted in both circumferential directions and, for transverse imperfections, in both longitudinal directions.

For concave-based cylinders where hydrogen embrittlement or stress corrosion can occur (see ISO 11114-1), the transition region between the cylindrical part and the cylinder base shall also be examined for transverse imperfections in the direction of the base. For the area to be considered, see Figure B.1. In this case, or when optional examination is carried out on the transition areas between the wall and neck and/or wall and base, this may be conducted manually, if not carried out automatically.



**Figure B.1 — Base/wall transition region**

One of the following two methods shall be used.


— Method A:

The ultrasonic sensitivity shall be set at + 6 dB to improve the detection of imperfections equivalent to 5 % of the cylindrical wall thickness in this thickened portion.

— Method B:

The ultrasonic system shall be calibrated using a standard reference artefact of a cylinder with a notch at sidewall-to-base transition (SBT) area shown in Figure B.2.

The depth of notch,  $T$ , for SBT shall be  $(10 \pm 1) \%$  of the guaranteed minimum wall thickness,  $a'$ , with a minimum of 0,2 mm and maximum of 1 mm, over the full length of the notch.



**Key**

- $D$  approximate notch location  
 $a$  guaranteed minimum wall thickness,  $a'$

**Figure B.2 — Schematic representation of reference notch for SBT**

The effectiveness of the equipment shall be periodically checked by putting a reference standard through the examination procedure. This check shall be carried out at least at the beginning and end of each shift. If during this check, the presence of the appropriate reference notch is not detected, all cylinders examined subsequent to the last acceptable check shall be retested after the equipment has been reset.

### B.3.2 Reference standard

A reference standard of convenient length shall be prepared from a cylinder which is dimensionally and acoustically representative of the cylinder to be examined, as demonstrated by the manufacturer. The reference standard shall be free of discontinuities which may interfere with the detection of the reference notches.

Reference notches, both longitudinal and transverse, shall be machined on the outer and inner surface of the reference standard. The notches shall be separated such that each notch can be clearly identified.


The dimensions and shape of notches are of crucial importance for the adjustment of the equipment (see Figures B.3 and B.4).

- The length of the notches,  $E$ , shall not be greater than 50 mm.
- The width,  $W$ , shall not be greater than twice the nominal depth,  $T$ . However, where this condition cannot be met a maximum width of 1,0 mm is acceptable.
- The depth of the notches,  $T$ , shall be  $(5 \pm 0,75) \%$  of the guaranteed minimum wall thickness,  $a'$ , with a minimum of 0,2 mm and a maximum of 1,0 mm over the full length of the notch. Runouts at each end are permissible.

— The notch shall be sharp edged at its intersection with the surface of the cylinder wall. The cross-section of the notch shall be rectangular, except where spark erosion machining methods are employed, when it is acknowledged that the bottom of the notch will be rounded.

— The shape and dimensions of the notch shall be demonstrated by an appropriate method.


NOTE  $T = (5 \pm 0,75) \% a'$  but  $\leq 1$  mm and  $\geq 0,2$  mm;  $W \leq 2T$ , but if not possible,  $\leq 1$  mm,  $E \leq 50$  mm.



**Key**

- 1 outside reference notch
- 2 inside reference notch

**Figure B.3 — Design details and dimensions of the reference notches for longitudinal imperfections**



NOTE  $T = (5 \pm 0,75) \% a'$  but  $\leq 1 \text{ mm}$  and  $\geq 0,2 \text{ mm}$ ;  $W \leq 2T$ , but, if not possible,  $\leq 1 \text{ mm}$ ,  $E \leq 50 \text{ mm}$ .

**Figure B.4 — Schematic representation of the reference notches for circumferential imperfections**

### B.3.3 Calibration of equipment

Using the reference standard described in B.3.2, the equipment shall be adjusted to produce clearly identifiable indications from inner and outer surface notches. The amplitude of the indications shall be as near equal as possible. If it is not possible to set the rejection levels individually, then the indication of smallest amplitude shall be used as the rejection level and for setting visual, audible, recording or sorting devices. The equipment shall be calibrated with the reference standard or probe, or both, moving in the same manner, in the same direction and at the same speed as will be used during the inspection of the cylinder. All visual, audible, recording or sorting devices shall operate satisfactorily at the test speed.

## B.4 Wall thickness measurement

If the measurement of the wall thickness is not carried out in another stage of production, the cylindrical part shall be 100 % examined to ensure that the thickness is not less than the guaranteed minimum value.

## B.5 Interpretation of results

Cylinders with indications that are equal to or greater than the lowest of the indications from the reference notches shall be withdrawn. This comparison shall be made between the indications from the cylinder and those from the reference notch in the same orientation and on the same face, e.g. a transverse inside imperfection shall be compared with the transverse inside reference notch. The cause of the indication shall be identified and, if possible, removed; after removal, the cylinders shall be re-subjected to ultrasonic flaw detection and thickness measurement.

Occasionally, a below minimum wall thickness indication can result due to the presence of a sub-surface imperfection (e.g. internal lamination) at the point. In such cases, the extent of the imperfection shall be evaluated.

Any cylinder, which is shown to be below the guaranteed minimum wall thickness, shall be rejected.

## B.6 Certification

The ultrasonic examination shall be certified by the cylinder manufacturer.

Every cylinder that has passed the ultrasonic examination in accordance with this specification shall be permanently marked with the characters "UT" or with the symbol as shown in Figure B.5 (where the characters "XY" represent the manufacturer's logo or symbol).




Figure B.5 — UT symbol

**Annex C**  
(informative)

**Type approval certificate**

**TYPE APPROVAL CERTIFICATE No. ....**

Issued by .....

(Inspector)

applicable International Standard .....

concerning

**SEAMLESS STEEL GAS CYLINDERS**

Approval No. .... Date .....

Type of cylinder .....

(Description of the family of cylinders [Drawing No.] which has received type approval)

$p_H$ : ..... bar  $D$ : ..... mm  $a'$ : ..... mm

Shape of base: ..... Min. base thickness: ..... mm

Overall length (min., max.): min. .... mm, max. .... mm

$V$  (min., max.): min. .... l, max. .... l

Material and heat treatment: .....

Material characteristics:  $R_{eg}$ : ..... MPa  $R_{mg}$ : ..... MPa

Manufacturer or agent: .....

(Name and address of manufacturer or its agent)

Reference to prototype test report(s): .....

All information may be obtained from .....

Results and conclusions .....

(Name and address of approving body)

Date ..... Place .....

(Signature of Inspector)



**Annex D**  
(informative)

**Acceptance certificate**

**ACCEPTANCE CERTIFICATE No. ....  
FOR SEAMLESS STEEL CYLINDERS**

A consignment of ..... cylinders consisting of ..... test batches has been inspected and tested  
(quantity)  
in accordance with ISO 9809- ..... related to Type Approval certificate No.: .....  
Designation or type of gas<sup>2)</sup>: .....  
Manufacturer's Nos.: ..... to .....  
Owner's Nos.<sup>2)</sup>: ..... to .....  
Manufacturer: ..... Manuf. order No.: .....  
Address: .....  
Country: .....  
Owner/Customer<sup>1)</sup>: ..... Purchase order No.: .....  
Address: .....  
Country: .....

**TECHNICAL DATA**

Water capacity  $V$ : nominal<sup>1)</sup>: ..... l Nominal length (without cap and without valve): ..... mm  
minimal<sup>1)</sup>: ..... l  
Test pressure  $p_h$ : ..... bar Nominal diameter  $D$ : ..... mm  
Working pressure at 15° C<sup>1)</sup>: ..... bar Min. guaranteed wall thickness  $a'$ : ..... mm  
Max. filling charge<sup>1)</sup>: ..... kg Drawing No.: .....  
Material: .....

Specified analysis <sup>3)</sup>	C %	Si %	Mn %	P %	S %	Cr % <sup>1)</sup>	Mo % <sup>1)</sup>	Ni % <sup>1)</sup>
max.:								
min.:								

Heat treatment: .....  
Stamp markings<sup>3)</sup>: .....  
.....

Date

The Manufacturer

### ACCEPTANCE TESTS

1. Measurements taken on one representative cylinder of the batch<sup>4)</sup>

Test No. or Batch No. or Cylinder No.	Cast No.	Water capacity [l]	Mass empty [kg]	Min. measured thickness [mm]	
				wall	base

2. Mechanical tests<sup>4)</sup>

Test No.	Cast No.	Tensile test			Hardness	Bend or flattening test	Impact test		Burst test			
		Yield strength $R_{ea}$ [MPa]	Tensile strength $R_{ma}$ [MPa]	Elongation $A$ [%]			180° without cracking	Charpy V at ....°C		$P_y$ [bar]	$P_b$ [bar]	failure mode
								Direction: .....				
								Avg. [J/cm <sup>2</sup> ]	Min. [J/cm <sup>2</sup> ]			
Min. values:												

3. Ultrasonic examination:

required (yes/no)<sup>1)</sup>: ..... passed (yes/no)<sup>1)</sup>: .....

This is to certify that the cylinders covered by this Acceptance Certificate have passed the hydraulic pressure test and all the other tests as required in Clause 10 of ISO 9809-.... and they are in full accordance with this part of ISO 9809 and the certified design-type approval.

Special remarks: .....

.....

On behalf of: .....

.....

Date: .....

.....

(Signature of Inspector)

1) Delete as applicable.

2) If required by the customer.

3) To be quoted or drawing to be attached.

4) Need not be filled in if test reports are attached.

## Bibliography

- [1] ISO 6406, *Gas cylinders — Seamless steel gas cylinders — Periodic inspection and testing*
- [2] ISO 10286, *Gas cylinders — Terminology*
- [3] ISO 11116-1, *Gas cylinders — 17E taper thread for connection of valves to gas cylinders — Part 1: Specifications*
- [4] ISO 11116-2, *Gas cylinders — 17E taper thread for connection of valves to gas cylinders — Part 2: Inspection gauges*
- [5] ISO 11117, *Gas cylinders — Valve protection caps and valve guards — Design, construction and tests*
- [6] ISO 11191, *Gas cylinders — 25E taper thread for connection of valves to gas cylinders — Inspection gauges*
- [7] ISO 13341, *Transportable gas cylinders — Fitting of valves to gas cylinders*
- [8] ST/SG/AC.10/1/Rev. 13, *Recommendations on the Transport of Dangerous Goods: Model Regulations*. Vols. 1 and 2

